Abstract Notification dated 30th September 1937.

The attention of the public is invited to the detailed notifications regarding the sale of several forest produce in the Division as per particulars noted below, published on pages 1673-1677, Part VI of the *Mysore Gazette*, dated 7th October 1937.

Particulars	Place of sale	Date of sale
1. Sale of the right of collection and removal of Bamboos in the several State Forests of the Division during 1937-38.	District Forest Office, Chikmagalur.	30th October 1937.
2. Sale of the right of tapping wood-oil in Mudgere and Koppa Ranges during 1937-39.	Range Office, Mudgere ..	30th October 1937.
	Koppa Town Musafirkhana	29th October 1937.
3. Sale of the right of collection and removal of canes in Koppa Taluk during 1937-39.	Koppa Town Musafirkhana	Do
4. Sale of the right of collection and removal of Tupra leaves in Mudgere and Koppa Taluks during 1937-40.	Range Forest Office, Mudgere	30th October 1937.
	Travellers' Bungalow, Koppa	Do

M. A. MUTHANNA,
District Forest Officer.

ENGINEERING DEPARTMENT

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 2nd October 1937.

Notice is hereby given that sealed tenders will be received at the office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 25th October 1937, for the work of providing Sanitary Installation in the Lady Wellingdon Tuberculosis Dispensary at Red Cross Building, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1937.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office, between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 150 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for the work of providing Sanitary Installation in the Lady Wellingdon Tuberculosis Dispensary at Red Cross Building, Bangalore," in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Estimate of the approximate quantities for providing sanitary installation in the Lady Willingdon Solonius Tuberculosis Dispensary at Red Cross Building, Bangalore.

Sl. No.	Particulars	Unit	Quantity
	GROUP I.		
	Soil, waste and water connection.		
1	Providing 4" C.I. soil pipe with specials, laying and jointing and scaffolding complete	R.ft.	100
2	Do do 3" waste pipe	,,	180
3	Providing and fixing 4" zinc cowel	No.	2
4	Fixing H.C. pan and sinks complete set	,,	12
5	Do do accessories	,,	13
6	Painting white enamel to C.I. and all pipe fittings	,,	12
7	Cutting floor and filling all round the pan and trap	,,	4
8	Providing 3" C.I. trap constructing cistern with cement and providing N. P. 6" dia. grating	No.	12
9	Wall bore and redoing	,,	16
10	Do do cornice	,,	6
11	Providing 1½" lead pipe with wiped solder joints	,,	8
12	Providing ¾" and ½" with wiped solder joints	,,	13
13	Providing and fixing ½" N. P. stop cock	,,	9
14	Do do bib cock	,,	11
15	Providing and fixing ½" lead cone to suit the W.C.	,,	4
16	Water connection with ¾" and ½" galvd. pipe with fittings and pipes from building outside up to fittings	,,	20
	Drainage Arrangement.		
1	Providing 4" S.W. pipes including cost of laying and jointing and earthwork excavation and refilling and cutting hard and soft rock, carting surplus earth and making ground to original surface	R.ft.	275
2	Constructing 6" and 4" S.W. gully trap cistern 12"×10" and fixing C.I. hinged lid and frame with cement including cost of gully trap and C.I. hinged lid and frame air tight and inside grating 6" diameter	No.	7
3	Constructing inspection chamber as per design with cement mortar up to 3' depth cost of all C.I. materials, etc., complete	,,	6
	GROUP II.		
	SETH CHELLARAM, KRISHANDOS MULTANI MATERNITY HOUSE.		
	Soil, waste and water connection.		
1	Providing 4" C.I. soil pipe with specials, laying and jointing complete with lead	R.ft.	60
2	Do do 3" do	,,	24
3	Providing and fixing 4" zinc cowel	No.	2
4	Fixing H.C. Lavatory and sinks complete set	,,	6
5	Fixing accessories	,,	6
6	Painting white enamel to C.I. and all pipe fittings	,,	6
7	Providing 3" C.I. trap constructing cistern in cement including providing and fixing 6" dia. N. P. gratings hinged	,,	4
8	Wall bore and redoing	,,	6
9	Providing and fixing lead cone to suit the W.C., etc., complete	,,	2
10	Providing 1½" lead pipe bending and fixing and making lead wiped solder joints	,,	4
11	Do do ¾" and ½"	,,	8

Sl. No.	Particulars	Unit	Quantity
12	Providing and fixing ½" N. P. stop cock	No.	5
13	Do do bib cocks	,,	4
14	Water connection with ¾" and ½" galvanized pipe with fittings from building outside up to fittings	,,	9
	Drainage Arrangements.		
1	Constructing inspection chamber as per design with cement mortar up to 3' depth including the cost of all materials, etc., complete.	,,	2
2	Constructing 6"×4" S.W. gully trap cistern 12"×10" and fixing C.I. hinged lid and frame with cement including cost of gully trap with grating and C.I. hinged lid and frame, airtight, etc., complete	,,	4
3	Providing 4" S.W. pipes including cost of laying and jointing with (to) cement mortar earthwork excavation and refilling cutting hard and soft rock carting surplus earth and making grounds to original surface	R.ft.	115
	GROUP III.		
	Providing Main Drains.		
1	Constructing man-hole of 4' diameter of the type design specified in the department with cement concrete bed brick in cement masonry including cost of C.I. man-hole cover and frame and C.I. steps complete.		
	Do do 4 feet depth	No.	1
	Do do 5 feet depth	,,	2
	Do do 6 feet depth	,,	6
2	Providing 6" S.W. pipes and laying and jointing complete	R.ft.	370
3	Boring hole in existing man-hole and redoing the same	No.	1
4	Repairing road with metal and gravel and tamping, etc., complete.	R.ft.	20
5	Earthwork and refilling	C.yd.	162
6	Do do. soft rock	,,	27
7	Do do hard rock	,,	27

Notification dated 7th October 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 2nd November 1937. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1938.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 2,500 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for constructing street sewers connecting No. 1 and 2 Sub-mains in Bangalore City," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Government of Mysore who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

Estimate for laying underground pipe sewers for remaining streets connected with No. 1 and No. 2 Sub-mains of Arlepet and Balepet areas.

No.	Particulars	Unit	Quantity	
			No. 1 Arlepet Street Sewers	No. 2 Balepet Street Sewers
1	Earthwork excavation in soil, gravel, wet earth, soft rock, slush, etc., for laying pipe sewers and refilling the same with proper consolidation with watering and tamping including barricading, lighting, shoring, water baling and cutting metalled portions and tarred road, etc., complete	C.yd:	1,105	1,076
2	Constructing circular man-holes 4′ diameter inside 1′ thick bed of cement concrete 1:2½:5 for 7′ diameter side walls with approved radial bricks (wirecut) in cement mortar of 1:4 proportion of 1½′ thickness top portion conical section including supplying and fixing cast iron frame 1′ 9″ diameter of 4 cwts. in weight with benching and cement concrete drain in bed of proportion 1:2½:5 up to ¾″ diameter of pipe cement plastering ½″ thick 1:2 proportion inside and exposed parts outside including supplying and fixing cast iron steps at intervals of 1′ 3″ including earthwork excavation, slush removing, shoring, water baling, refilling and tamping earth with watering, barricading and lighting including painting iron materials, etc., complete.			
	Do up to 5′ depth	Each	46	54
	Do from 5′ to 6′ depth	,,	..	2
3	Providing and fixing 7″ glazed stoneware pipes of "tested" quality laying and caulking with hemp, jointing with cement mortar 1:2 proportion including testing with water, etc., complete	R.ft.	2,007	2,300
4	Providing and fixing 7″×4″ junction pipes of "tested" quality laying and caulking with hemp, jointing with cement mortar 1:2 proportion including testing with water, etc., complete	Each	190	184
5	Providing and fixing 4″ diameter stoneware pipes of tested quality, laying and caulking with hemp, jointing with cement mortar 1:2 proportion with earthwork excavation, refilling, watering and tamping, etc., complete for house connections including wall bores and repairing, etc., complete	R.ft.	2,850	16,500
6	Providing and fixing 6″×4″ stoneware gully traps with cast iron gratings, constructing cisterns with burnt brick in cement mortar 1:4 proportion cement plastering ½″ thick 1:2 proportion inside and outside and fixing	..		

No.	Particulars	Unit	Quantity	
			No. 1 Arlepet Street Sewers	No. 2 Balepet Street Sewers
	gully traps with cement concrete 1 : 2½ : 5 proportion 6" all round and bed including necessary wall bores, etc., complete and including glazed stoneware bends	Each	190	1,100
7	Making bores in man-holes or in pipe sewers for inserting house connections and redoing the same with cement concrete, etc., complete including 4" stoneware bend "tested" ..	„	..	916
8	Carting surplus earth to any distance within the municipal limits as pointed out	C.yd.	615	526

Notification dated 11th October 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M., on 8th November 1937, for laying underground Sub-main No. 5 and street sewers in Avenue Road, Bangalore City. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1938.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 3,500 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for laying Sub-main No. 5 and street sewers, Avenue Road, Bangalore City," in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Government of Mysore who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Sanitary Engineer will be final and legally binding.

12. For the speedy completion of the work, it may be required to distribute the work among two or more contractors.

Statement of quantities for laying sub-main No. 5 and its connected street sewers in Avenue Road, Bangalore City.

No.	Items of work	Per	Quantities	
			Sub-main No. 5	Street sewers
1	Earthwork excavation in soil, gravel, wet earth, soft rock, slush, etc., for laying pipe sewers and refilling the same with proper consolidation with watering and tamping including barricading lighting, shoring, water baling and cutting metalled portion and tarred road, etc., etc., complete	C.yd.	3,016	6,587
2	Providing 9″ glazed stoneware pipes of tested quality, laying and caulking with hemp, jointing with cement mortar 1 : 2 proportion including testing with water, etc., complete	R.ft.	1,860	..
3	Do do 12″ stoneware pipes do	,,	1,514	..
4	Do do 7″ stoneware pipes do	,,	..	11,754
5	Constructing circular manholes 4′ diameter inside 1′ thick bed of cement concrete 1 : 2½ : 5 for 7′ diameter side walls with approved radial wirecut bricks in cement mortar of 1 : 4 proportion of 1½′ thickness top portion conical section including supplying and fixing cast iron frame and cover 1′—9″ diameter of 4 cwts. in weight with benching and cement concrete drain bed of proportion 1 : 2½ : 5 up to ¾ths diameter of pipe, cement plastering ½″ thick (1 : 2 proportion) inside and exposed parts outside including supplying and fixing cast iron steps at intervals of 1′—3″ including earthwork excavations, slush removal, shoring, water baling refitting and tamping earthwork, watering, barricading and lighting and including painting iron materials, etc., complete from 4′ to 5′ dpth ..	Each	10	51
	Do 5′ to 6′ depth	,,	6	35
	Do 6′ to 7′ do	,,	8	5
	Do 7′ to 8′ do	,,	3	..
	Do 8′ to 9′ do	,,	2	..
	Do 9′ to 10′ do	,,	1	..
5(a)	Do with burnt brick in cement mortar for the above depths	Each		
6	Providing and fixing 6″×4″ stoneware gully traps with cast iron gratings constructing cisterns in burnt brick in cement mortar 1 : 4 proportion, cement plastering ½″ thick 1 : 2 proportion inside and outside and fixing gully trap with cement concrete 1 : 2½ : 5 proportion 6″ all round and bed including necessary wall bore, etc., complete	No.	224	784
7	Providing 4″ diameter stoneware pipes of tested quality laying and caulking with hemp jointing with cement mortar 1 : 2 proportion, with earthwork, refilling, watering and tamping, etc., complete for house connections including wall bores and repairing, etc., complete ..	R.ft.	4,480	15,680
8	Making holes in pipe sewers or in manholes and inserting house connections pipe lines with cement concrete 1 : 2½ : 5 and cement plastering 1 : 2 proportion, etc., complete	Each	224	784
9	Constructing ventilating shafts by providing 16′ lengths and 4″ diameter boiler tube pipes with C. I. specials and 4″ zinc ornamental cowl including masonry with burnt brick in cement mortar 1 : 4 proportion and ½″ thick cement plastering 1 : 2 proportion, etc., complete	Each	1	6

No.	Items of work	Per	Quantity	
			Sub-main No. 5	Street Sewers
10	Constructing flush tanks of 200 gallons capacity with burnt brick in cement mortar walls 9" thick, cement plastering ½" thick 1 : 2 proportion including providing stoneware bend tubes syphon 6" diameter both inlet and outlet ends as per standard design and including 1' 9" diameter cast iron frame and lid 4 cwts. in weight for inlet and outlet chambers, etc., complete	Each	1	3
11	Carting surplus earth, etc., to any distance within the Municipal limits as pointed out during execution ..	C.yd.	754	2,124
12	Providing and fixing junction pipes of tested quality, right angled, oblique or Y laying and caulking with hemp jointing with cement mortar 1 : 2 proportion including testing with water, etc., complete junction pipes of 12"×4"	Each	..	..
	Do 9"×4"	,,	..	..
	Do 7"×4"	,,	..	..

Notification dated 11th October 1937.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 1st November 1937, for the work of constructing drains at Dodballapur Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1938.

2. The plans, detailed estimate and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 640 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for the work of constructing drains at Dodballapur Town" in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the Sanitary Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water. etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

Estimate of the approximate quantities for constructing Drains at Dodballapur Town.

Sl. No.	Particulars	Unit	Quantity
1	Constructing semi peg-top section drains with cement concrete 1 : 2½ : 5 and the invert and sides plastered over with cement mortar ½" thick 1 : 2 proportion on lime concrete bed of 6" thick including earth work, etc., complete as per design—		
	3" section drains	R.ft.	1,975
	4" (1) do	,,	390
	4" (2) do	,,	1,610
	5" (3) do	,,	1,180
	5" (4) do	,,	510
	8" do	,,	760
	10" do	,,	300
2	Constructing silk pattern drains with available slabs for checks on 6" thick lime concrete bed with 4½" thick cement concrete 1 : 2½ : 5 and moulding including cement plastering ½" thick (1 : 2 proportion), etc., complete as per design—		
	3" section drains	,,	3,010
	4" (1) do	,,	410
	4" (2) do	,,	220
	Size sone in mud	C.ft.	1,875

N. KRISHNIENGAR,
Sanitary Engineer.

MYSORE DIVISION.

Abstract Notification dated 29th Septeber 1937.

RESTORING DADA MUDIKE, GUNDAKALKERE, NAGAMANGALA TALUK.

The attention of the public is invited to the tender notice, published in pages 1523 to 1525 of Part VI of *Mysore Gazette*, dated 16th September 1937, calling for tenders for Restoring Dada Mudike, Gundakalkere in Nagamangala Taluk. The last date for receiving tender is extended up to 2 P.M. on Saturday the 25th October 1937.

Notice dated 13th October 1937.

Sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 12 NOON on 22nd November 1937, for the construction of a Girder bridge with well curbs foundations, piers and abutments across River Shimsha at Halagur, 2/55 of Bangalore-Mysore Road, *via* Kankanhalli.

2. Tenders in the prescribed form obtainable from the office of the Executive Engineer, Mysore Division, should be addressed to the Executive Engineer, Mysore Division, in a sealed cover and superscribed as "Tender for the constructing of a Girder bridge. The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 7,800 (Rupees seven thousand eight hundred only) in cash or deposited in the Government Treasury under "17 (*a*) Public Works Deposits" in Government Promissory Notes, or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 22nd November 1937 at Mysore. The final acceptance of the tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931).

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Enginee's Office, Mysore, on all working days, between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Rupees.....

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10 Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department Schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions, or additions at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of June 1939, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 100 per day, for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery, that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(A) The contractor should at his own cost :—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills, and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.

(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

Note.—(B) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract estimate for the construction of a Girder Bridge with well Curbs for foundations, piers and abutments across the River Shimsha at Halagur 2/55 of Bangalore-Mysore Road, *via* Kankanhalli (18′ Road way).

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavating foundations for wells of abutments and piers	C.yd.	0–12–0	652	489
2	Erecting cement concrete curbs 1 : 2 : 4, 5′—0″ external diameter, 4′—6″ internal and 3″ thick, 1½′ high cast in site including frame work and fixing charges, etc., complete ..	R.ft.	6 8 0	1,452	9,438
3	Filling hollows of curbs with surki concrete ..	C.ft.	0 5 0	23,203	7,251
4	Compound main girders 26″×12″×174·5 lbs. ..	...	...	...	..
	Do end girders 23¼″×12″×128 lbs. including hoisting charges and a prime coat of anti corrosine or any other approved paint	Ton	200 0 0	139·40	27,880
5	Carting girders from Chennapatna Railway Station to Halagur, a distance of 15 miles ..	Ton mile	1 0 0	2,091	2,091
6	Mild steel bearing plates 26″×18″×1″ for seating of girders	Each	7 8 0	52	390
7	Reinforced cement concrete (1 : 2 : 4) decking 8¼″ thick as per design with necessary expansion joints, etc., complete with 18′ road way (530′×18½′×8¼″)	C.ft.	2 4 0	6,741	15,167
8	Railing with 1½″ pipe on angle iron standards 3″×3″×3″ high, etc.	R.ft.	2 0 0	1,080	2,160
9	New stone revetment for wings	C.yd.	2 0 0	76	150
10	Pitching 2′ deep the bed between the piers ..	„	2 0 0	569	1,138
11	Rataining wall for pitching	R.ft.	2 4 0	1,080	2,430
12	Ring bund, un-watering and diversion of river ..	..	L. S.	...	2,000
13	Temporary sheds	Do	..	..	500
14	Approach roads	„	..	..	350
15	Un-foreseen charges	„	..	...	866

B. KRISHNA RAO,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated the 23rd September 1937.

The attention of the public is hereby invited to the detailed notification calling for tenders for restoring Chatnahalli Hirekere Register No. 38 of Honnali Taluk, filling up the breach and levelling the draft channel of the weir, published in pages 1611-1612, Part VI of the *Mysore Gazette*, dated 30th September 1937.

The last date for receiving tenders is Monday the 25th October 1937.

P. SUBBA RAO.
Executive Engineer.

ANJANAPUR DIVISION.

Abstract Notification dated 3rd October 1937.

The attention of the public is hereby drawn to the Notification dated 27th September 1937, published in Part VI of the *Mysore Gazette*, dated 7th October 1937, pages 1684-1688, calling for tenders for constructing an Inspection Lodge at Anjanapur Reservoir Works. The earnest money to be deposited is Rs. 700 (Rupees seven hundred only).

The last date for receiving tender is up to 4 P.M. on the 22nd October 1937.

Notification dated 17th October 1937.

In modification of this office Notification dated 27th September 1937, published on pages 1684 to 1688 of Part VI of the *Mysore Gazete*, dated 7th October 1937, calling for tenders for "Constructing an Inspection Lodge at Anjanapur Reservoir Works, Anjanapur," it is notified that the time for acceptance of tenders at this office is extended till 4 P.M. on Friday the 29th instant.

Page No. 1686—Item Nos. 10 and 15 and page No. 1687—Item No. 23, please *omit* words "Iron," "light" and "S. L." and *read* as "brass", "white" and "L. S." in their stead respectively.

The words "pipe to be supplied departmentally" may be inserted after "3" diameter cast iron old pipe" in item No. 15 on page 1686.

M. K. RAJAM IYENGAR,
Executive Engineer.

MEDICAL DEPARTMENT

VANI VILAS AND CHILDREN'S HOSPITAL, BANGALORE.

Abstract Notification dated the 27th September 1937.

Sealed tenders, in triplicate, on half-sheet sized foolscap paper will be received at the office of the Secretary, Victoria, Minto and Vani Vilas Hospitals, Bangalore (in the Victoria Hospital) by the undersigned at 11 A.M. on Saturday the 30th October 1937, for the supply of "Bedding and Clothing" required for the use of the said hospitals for the year 1937-38. For further particulars, please refer to the detailed notification published in pages 1613-1616, Part VI of the *Mysore Gazette*, dated the 30th September 1937 and to the following corrections.

Page Nos. 1614 and 1616—Item Nos. 18 and 13, please *omit* words "Unbleached" and *read* as "Bleached."

H. N. PALLEGAR,
Secretary.

EPIDEMIC DISEASES HOSPITAL AND LEPER ASYLUM, BANGALORE.

Abstract Notification dated 2nd October 1937.

The attention of the public is invited to the detailed notification calling for tenders for the supply of diet and other articles to the combined Epidemic Diseases Hospital and Leper Asylum, Bangalore, from 1st January 1938 to 31st December 1938 (both days inclusive), published in pages 1689-1690 of Part VI of the *Mysore Gazette*, dated 7th October 1937.

T. SUBBA RAO,
Medical Officer.

MEDICAL STORES.

Notification dated 24th September 1937.

Notice is hereby given that sealed tenders, in triplicate, will be received at 1 P.M. on Thursday the 25th November 1937, by the Superintendent, Medical Stores, for the supply, by contract, of country medicines, etc., (as per list below) for the Medical Stores, Mysore Government, from 1st January to 31st December 1938 (both days inclusive).

2. No tender will be received after the date and hour abovementioned.
3. Tender to be superscribed "Country Medicines," etc.
4. No tender will be received unless accompanied by a treasury receipt for Rs. 150 depositing into the treasury as earnest money on behalf of this tender. Cash will not be accepted in lieu of Treasury receipt.
5. Tenders will be opened by the Superintendent, Medical Stores, on the date and at the hour abovementioned.